

Cement Stabilized Base & Chipseal

County Road 54... The Saga Continues

MCEA Annual Conference
January 23, 2020

John Brunkhorst, PE - McLeod County Engineer/PW Director
Dave Rettner, PE - American Engineering Testing Inc.



Topics


1. Background
2. Project History
3. Construction Highlights
4. Construction and Performance Testing
5. Costs
6. Lessons Learned
7. Next Steps



Where is McLeod County?



About 3.5 hours SE
of Fargo, ND



Located approximately 60 miles west of the Twin Cities


Where is Project ?

County Road 54 (CR 54)

~ 6 miles South of Hutchinson, MN

**Entire Corridor
~4 miles
CR 87 to CSAH 7**

**Initial Project
~1 mile**



BACKGROUND

CR 54 Issues

- ~200 ADT
- ~\$5,000 Annually for Dust Control (CaCl_2)
- Washboards (due to speed/braking)
- Frequent Blading Required
- No Funding for traditional base and surfacing
- County Funded (non State Aid route)



2013 - Neighborhood meeting
- Frustrated with condition of CR 54

GOALS FOR CR 54 & other higher volume gravel roads

- Dust Free Road
- Washboard Free
- Stand up to Agricultural Traffic
- ***Cost Effective***

Project History

2014 Prime/Seal Project

- Emulsified Prime Coat
- Single Chip Seal
- Fog
- ***Portions began to break up in fall***



Project History

2015 Tiling and Reclamation Project



NOW WHAT?



**WAS IT OVER WHEN THE GERMANS BOMBED
PEARL HARBOR?**


HELL NO!

Project History

2016 Cement Stabilized Full Depth Reclamation, Seal Coat & Fog

Project Goal – Find the most cost effective optimal cement content and stabilization depth.

- 4 Test Sections
- Varying Cement Contents
- Varying Stabilization Depths
- Short Section of Single Chip Seal
- 4% Cross Slope



PROJECT OVERVIEW

	Section 1	Section 2	Section 3	Section 4
Cement Content	8 %	7 %	6 %	5 %
Stabilization Depth	10"	10"	8"	8"
Tack Coat	1300'	1300'	1300'	1300'
Double Chip Seal	1300'	1300'	1300'	1200'
Single Chip Seal	-	-	-	100'
Fog Seal	1300'	1300'	1300'	1300'



CONSTRUCTION

Spreading Cement



CONSTRUCTION

Cement Incorporation



CONSTRUCTION

Breakdown Rolling



CONSTRUCTION

Breakdown Rolling



CONSTRUCTION

Initial Blading



CONSTRUCTION

Finish Rolling



CONSTRUCTION



Finish Rolling & Final Trimming

CONSTRUCTION



Final Trimming

CONSTRUCTION

Finished CSFDR



CONSTRUCTION

Finished CSFDR



CONSTRUCTION

Seal Coat – Broom prep



CONSTRUCTION

Tack Coat



CONSTRUCTION

Seal Coat – First Layer



2016/08/22

CONSTRUCTION

Seal Coat – Second Layer



CONSTRUCTION

Seal Coat – Second Layer



CONSTRUCTION

Fog Seal

8/23/16

LESSONS LEARNED

2016 Project

Ride

- Finish longer sections
- Tough to correct after project
- Likely include Ride Spec in Future



LESSONS LEARNED

Subgrade

- Need Good Drainage
- Continue Centerline Tile

Residential Driveways

- Figure out Transition
- Potential Plowing Damage

Future Projects

- No County Operators, One Contract
- Ensure Samples Match Existing Conditions
- 2nd Seal – Year 2 or later

2016 Project



2016 PROJECT COSTS

CSFDR

	<u>Cost/Mile</u>	<u>Cost/SY</u>
• Cement	\$ 51,300	\$ 3.12
• Stabilization	\$ 16,300	\$ 0.99
• Laydown/Compaction *	\$ 15,000	\$ 0.93

CHIP SEAL

• Tack Coat	\$ 3,100	\$ 0.19
• 3/8" Seal	\$ 22,900	\$ 1.40
• 1/4" Seal	\$ 20,000	\$ 1.22
• <u>Fog Seal</u>	<u>\$ 3,300</u>	<u>\$ 0.20</u>

TOTAL

~\$ 132,000


~\$ 8

* County Roller Operators



50 YEAR LIFE CYCLE COSTS per mile

COMPARISONS



NEXT STEPS

Finish CR 54

Continue to Monitor

More Planned

- ~14 Miles in 5-Year Plan

Good Tool in Tool Box for Right Road

- \$140,000/mile vs. Traditional Paving ~\$450,000+



2018 Project

2018 Cement Stabilized Full Depth Reclamation, Seal Coat & Fog

- Finish Remaining 3 Miles
- Micro Mill south 1 mile
- Traditional Design/Bid/Build
- Micro Mill south 1 mile
- Hybrid Specifications from
MnDOT/NDDOT/Consultant
 - Contractor Mix Design
 - Ride spec - Straightedge
 - Cross slope spec

STATE OF MINNESOTA
COUNTY OF McLEOD

*****PROPOSAL*****

FOR HIGHWAY CONSTRUCTION
AND MAINTENANCE PROJECTS WITH
BIDS RECEIVED UNTIL 1:00 O'CLOCK P.M. ON
March 27th, 2018
AT MCLEOD COUNTY HIGHWAY DEPARTMENT (HATS)
1400 ADAMS STREET SE-HUTCHINSON, MN 55350

PROPOSAL OF _____

NAME _____ PHONE _____

ADDRESS _____

TO FURNISH AND DELIVER ALL MATERIALS AND TO DO AND PERFORM ALL WORK IN ACCORDANCE WITH THE CONTRACT, THE PLANS, AND THE APPROVED DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION", 2016 EDITION, ON FILE IN THE OFFICE OF THE COMMISSIONER OF TRANSPORTATION, OR ON FILE IN THE OFFICE OF THE COUNTY HIGHWAY ENGINEER EXCEPT AS STATED OTHERWISE IN THE SPECIAL PROVISIONS WHICH ARE PART OF THIS PROPOSAL, FOR:

COUNTY PROJECT NO. CP 17-054-01 Cement Stabilized Reclaim & Seal Coat
CP 18-062-01 Cement Stabilized Reclaim & Seal Coat

LOCATION: County Road 54 & County Road 62

TYPE OF WORK: Cement Stabilized Reclaim & Seal Coating

STARTING DATE: 2018 Season (See Special Provisions)

COMPLETION DATE: (See Special Provisions)

NOTICE TO BIDDERS: In lieu of returning the complete proposal, you may return only the portions of the proposal that require Bidder input. You must initial changes made in the Schedule of Prices in the Proposal and acknowledge addenda on the back cover sheet. You may submit a computer generated printout of the schedule of prices in lieu of inking or typing the Department's bid schedule.

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

Phil Schmalz
Phil Schmalz, P.E. License #50403
Date: 2-27-18

2018 Project

2018 Cement Stabilized Full Depth Reclamation, Seal Coat & Fog

Contract Awarded to Allstates Pavement Recycling & Stabilization
on May 8, 2018

County Road 54 – stand alone – Engineers Estimate: \$496,243.50

<u>Contractor</u>	<u>54 Bid</u>
Allstates Pavement Recycling/Stab, Rogers, MN	\$395,497.86
Astech Corporation, St. Cloud, MN	\$426,778.98
Duininck, Inc., Prinsburg, MN	\$432,211.76

How did it go?

Early Concerns with Cement Laydown



How did it go?

Sealcoat Debonding



Now What?

County Didn't Get What They Want

Vs.

Contractor "Met Spec"

Received OPERA Funds to Test and Tell Story



2018 - Testing & Findings

Spring 2019

Chipseal Continued Debonding over the Winter/Spring



2018 - Testing & Findings


Work Plan

- Evaluate all construction testing data and inspector diaries
- Ground Penetrating Radar to Determine Depth of Stabilization
- Falling Weight Deflectometer Testing to Determine Current Strength of Roadway
- DCP Testing to Determine Strength of Cement Stabilized Base by Depth and Confirm Depth of Stabilization (and aid with GPR analysis)
- Coring (if possible) to Evaluate the Quality of the Stabilized Material
- Unconfined Compressive Strength Testing (if possible) to compare to Mix Design
- Report with findings

Construction Data

- Long Stretches of Cement Stabilization were done at one time.
 - Goal is to be mixed graded and compacted within 1 hour in the summer
- Unclear how well final compaction was completed after blade work and timing of final compaction
- Unclear how well surface was swept after micro-milling – might have affected bonding of chipseal

Ground Penetrating Radar



FWD Testing

- Definite Strength Difference Between Northern and Southern Portions of Roadway
- Combination of Differences in Subgrade and Stabilized Layer Strength

	Northern 7,500 Feet			Southern 8,000 Feet		
	Spring Load Capacity (tons)	Effective GE (Inches)	Effective R Value	Spring Load Capacity (tons)	Effective GE (Inches)	Effective R Value
Average	10.4	29.4	7.4	6.1	19.1	5.6
Std. Dev.	3.3	6.9	1.9	2.0	6.6	1.7
Design	7.1	22.6	5.5	4.0	12.5	3.9

DCP Testing

- Most DCP Tests Showed Significant Differences in Strength with Depth

[illegible]

Coring



AET No. 27-20035

County Road 54
C-1



AET No. 27-20035

County Road 54
C-3




AET No. 27-20035

County Road 54
C-6

Unconfined Compressive Strength

Cores that were Removed
Intact were at or Near Design
Strength (250 psi)

Core	UCS (psi)
C-1	274
C-3	193
C-4	158
C-5	98
C-7	297
C-8	338
C-9	225



Findings

- It Appears that the Time Between the Start of Mixing and Final Compaction was too Long. Stretches Being Worked were too Long to be Completed in One Hour.
- Divots in Road Surface were from Poorly Compacted Material Filling Padfoot Roller Depressions – Related to Time to Finish
- Variability in Strength both at Surface and at Depth – Possibly Due to too Much Time from Start of Mixing Until Final Compaction
- Design Strength was Achieved in Many Locations
- Often only 6 inches of Stabilization Met Strength
- Dirty Surface of Roadway After Micro-milling Might have Hurt Bonding of Chipseal

Next Steps/Alternatives

1. Work with Contractor for Resolution
2. Identify Appropriate Fix for Current Conditions
 - a. Do Nothing
 - b. Add gravel to current surface
 - c. Reclaim entire road back to gravel
 - d. Pave entire road (CR 87 to CR 7)
 - e. Pave 1st mile only (CR 87 to 1 mile N)



PUBLIC WORKS

QUESTIONS?



John Brunkhorst, PE
County Engineer/Public Works Director

Dave Rettner, PE
President/Principal

McLeod County Public Works
(320) 484-4321
www.co.mcleod.mn.us/highway
john.brunkhorst@co.mcleod.mn.us

American Engineering Testing, Inc.

(651) 755-5795
www.amengtest.com
drettner@amengtest.com

